



North Dakota State Laboratory

HB1004

House Appropriations - Human Resources Subcommittee

01.19.2023

- Introductions
- Project Vision & Goals
- Design Process

Space Programming

Design Concepts

- Site Selection Process
- Preliminary Cost Estimate
- Operating Cost Projections
- Schedule



Project Vision & Goals

State laboratories support critical department functions...

To accomplish our mission, the **North Dakota Department of Health** is committed to: **improving the health status** of the people of North Dakota; **improving access to and delivery of** quality health care and wellness services; **promoting a state of emergency readiness** and response; **achieving strategic outcomes** using all available resources; **strengthening and sustaining stakeholder engagement** and collaboration; and **managing emerging public health challenges**.

The North Dakota Department of Environmental Quality's vision is for a *sustainable, high quality environment* for current and future generations. Our mission is to conserve and protect the quality of North Dakota's *air, land, and water resources* following science and the law.



....but our facilities are *approaching the end* of their useful life.









Lack of Space for Office Functions

• Officing tasks occur in labs (safety issue)



Incoming Sample/Specimen Workflows

- Lack of dedicated sample/specimen receipt areas.
- DOH specimen receipt in hallways
- Separated sample storage required to preserve DEQ sample integrity



Lack of Space for Growth

- Instrumentation updates in DOH fill current lab footprints
- No space for new DOH programs (ie Corrections, LNR-C, Biosurveillance, Newborn Testing)
- DEQ testing to parts-per-trillion level requires clean spaces and separated functions to avoid cross-contamination
- Anticipated growth in DEQ volumes due to updated PFAS, copper, and lead regulations



BSL-3 Lab Deficiencies

- Lack of vestibules/anterooms in existing BSL-3 Labs
- Single-aisle labs limit flexibility and efficiency



Lack of Citizen-Focused Engagement


 No space for outside visitors to experience lab functions, understand workflows, or develop interest in STEM functions



Mechanical System Deficiencies & Reliability

- Lack of separation of airflows between DOH & DEQ leads to cross-contamination risk
- Reliability issues for power and mechanical equipment compromises testing capability

















A new State Lab facility will preserve and advance our ability to protect North Dakota's public health & environment.





The proposed laboratory will provide Public Health & DEQ with:


- Improved regulatory compliance to ensure continued access to testing programs
- Additional programs and access to testing
- Adequate space to support current and future testing needs
- Optimized workflows to enable more efficient testing
- Safe and inviting working environment for staff.
- State-of-the-art utility systems with minimized cross-contamination risks
- Citizen-focused spaces to share our work, collaborate with universities, and inspire future scientists



Design Process

Existing Building Analysis











Visual Program & Adjacency Diagrams



Visual Program & Adjacency Diagrams (DOH Detail)





DEQ Lab Vision:

Suites equipped with technology to support specific testing.
Each suite - Larger prep area, smaller test area. Approx 1/3 prep, 2/3 test
Establish size of suite based on quantity of instrumentation within - see
diagrams

Vacuum pumps - noise control required (closet for vac pumps or sound insulated cabinets)

Prep Rooms

(1) or (2) fume hoods, sometimes two fume hoods, or canopy hood Bench snorkels as shown on diagram

Instrument/Test rooms

Always have a sink somewhere, but have movable tables for instrumentation.

Space for (1) refrigerator or freezer for reagent storage Overhead carriers with gas connection


Suites discussed (Instrument qty per DEQ input)

- 1) LC, GC, GCMS (8) Instruments
- 2) GCMS/MS (6) Instruments
- 3) ICP, ICPMS (6) Instruments Low metal lab
- 4) LCMS/MS (6) Instruments Clean Lab, Low PFAS Lab
- 5) ICMS/MS (4) Instruments Clean Lab
- 6) VOC (4) Instruments Clean Lab
- 7) FIA and IC (6) Instruments
- 8) Petroleum (4) Instruments
- 9) Feed/Fertilizer (4) Instruments
- 10) Miscellaneous Testing (4) Instruments
- 11) Kit Prep (4) Instruments
- 12) Dirty (4) Instruments


Additional Functions

- 1) Griding
- 2) Sample Login
- 3) Admin Assistant
- 4) Demands Lab
- 5) Engines


Typical Layout - (2) Instrument Lab



Typical Layout - (4) Instrument Lab



Typical Layout - (6) Instrument Lab



OGRAM SUMMARY	Ex	Existing		Proposed	
Main Lab Building	Staff	Square Feet (net)	Staff	Square Feet (net)	SF
Departments					
Department of Health (DOH)	23	5,545	35	33,864	28,319
Department of Environmental Quality (DEQ)	12	7,671	16	26,571	18,900
Shared Lab Support		1,648		968	-680
Public/Lobby Spaces		0		2,209	
Office Space (Existing)		6,800			-6,800
Shared Staff Space		0	2,480		2,480
Shared Building Support/Mechanical		5,287	5,921		634
Program Contingency				2,500	
Subtotal Departmental Space Needs*	35	26,951	51	74,513	47,562
Building Gross Up (est) - walls, circulation, etc)	25%	6,258	35%	26,080	19,822
Total Building Needs (GSF)		33,209		100.593	67,384

^{*} Departmental Square Footage includes 35% secondary circulation gross up.

^{**} Staff headcounts include staff with dedicated office/cubicle space. Lab Techs without assigned office/cubicle are not included in these headcounts.

	Existing
Existing Ancillary Support Buildings	Square Feet (gross)
DOH/DEQ Storage Building - 2635 E Main	3,200
DOH Warehouse - 26th & Vermont	10,000
DOH Mobile Lab 1	442
DOH Mobile Lab 2	442
Total Ancillary Support Building Square Footage	14,084

Total Existing Square Footage	47 202
	47,293



Space Type	Area	Comment
Lab space	53,100 sf	(A) (B) (C)
Office Space:	8,493 sf	
Training Lab and Conferencing:	2,200 sf	D
Support space (lab support, mechanical/electrical, circulation):	36,800 s ⁻	f E F G
Total proposed:	100,593 s ⁻	f



Additional Lab Space

- Separated lab functions address cross-contamination concerns
- Dedicated space for sample receipt & storage
- Growth space for new programs



BSL-3 Growth Factors

- Lack of vestibules/anterooms in existing
- Additional area to improve workflow



General storage/supplies co-located with labs

• Allows more efficient utilization of storage square footage



Public-Facing Training and Conferencing

• Space provided for visitor training and conferencing, plus training lab for staff and outside training.



DOH Warehouse Exit Strategy

• Bulk storage space provided in program. Reduced COVID demands will drive eventual elimination of need for offsite warehouse space allowing 26th & Vermont warehouse lease to be terminated



Mechanical Equipment Strategy

• Indoor space for boilers, fire suppression, air compressors, vacuum process chillers, etc. Rooftop chillers, air handlers, exhaust fans with service vestibules. Design team is studying potential rooftop penthouse to allow indoor mechanical units



Building Gross-Up

• Additional gross-up to support vertical circulation, shafts, and wider hallways



Conceptual Floor Plans










- Currently planning for three story facility
 - Level 1 DOH/DEQ Labs, Training Labs, Warehouse
 - Level 2 DEQ Labs & Offices
 - Level 3 DOH Labs & Offices




Site Selection

Sites Considered | First Round



Sites Under Consideration





Cost Estimate



- Cost estimates performed in predesign process were utilized to establish Governor's budget request
 - \$15 million (received in 2021-22 bienium)
 - + \$55 million budget request \$70 million total project budget
- State has retained Kraus Anderson Construction as construction manager at risk for the project
- Early validation of predesign cost estimates confirms \$70 million project budget is adequate*

*Construction costs contingent on funding approval 2Q 2023



Operating Cost Analysis



Energy Use

- Existing Building Energy Use Intensity = 402 kbtu/sf/yr
- Proposed Energy Use Intensity =180-240 kbtu/sf/yr
- Energy Cost = \$367,000/yr (~\$3.65/sf/yr)

Additional Operating Cost (Trash, snow removal, etc)

- Cost target dependent on site chosen and ability to share resources with adjacent state buildings
- Range of \$5-\$15/sf/yr

Operating Cost Projection

Low: $$9/sf \times 100,600 sf = $905,000 per year$

High: $20/\text{sf} \times 100,600 \text{ sf} = 2,012,000 \text{ per year}$



Schedule

Milestone	Date
Finalize Site Selection	Q1 2023
Funding Secured	Q2 2023
Design Complete	Q3 2023
Construction Start	Q3 2023
Construction Complete	Q4 2025
Building Occupancy	Q1 2026
	All approximate dates contingent on funding



Thanks!
Question/Answer