

B|W|B|R



# North Dakota State Laboratory

HB1004

Senate Appropriations - Human Resources Subcommittee

03.08.2023

- Introductions
- Project Vision & Goals
- Design Process
  - Space Programming
  - Design Concepts
- Site Selection Process
- Preliminary Cost Estimate
- Operating Cost Projections
- Schedule

# Project Vision & Goals

## State laboratories support ***critical department functions...***

To accomplish our mission, the **North Dakota Department of Health** is committed to: ***improving the health status*** of the people of North Dakota; ***improving access to and delivery of*** quality health care and wellness services; ***promoting a state of emergency readiness*** and response; ***achieving strategic outcomes*** using all available resources; ***strengthening and sustaining stakeholder engagement*** and collaboration; and ***managing emerging public health challenges***.

The **North Dakota Department of Environmental Quality's** vision is for a ***sustainable, high quality environment*** for current and future generations. Our mission is to ***conserve and protect*** the quality of North Dakota's ***air, land, and water resources*** following science and the law.

....but our facilities are ***approaching the end*** of their useful life.





- A** Lack of Space for Office Functions

  - Officing tasks occur in labs (safety issue)
- B** Incoming Sample/Specimen Workflows



  - Lack of dedicated sample/specimen receipt areas.
  - DOH specimen receipt in hallways
  - Separated sample storage required to preserve DEQ sample integrity
- C** Lack of Space for Growth

  - Instrumentation updates in DOH fill current lab foot-prints
  - No space for new DOH programs (ie Corrections, LNR-C, Biosurveillance, Newborn Testing)
  - DEQ testing to parts-per-trillion level requires clean spaces and separated functions to avoid cross-contamination
  - Anticipated growth in DEQ volumes due to updated PFAS, copper, and lead regulations
- D** BSL-3 Lab Deficiencies

  - Lack of vestibules/anterooms in existing BSL-3 Labs
  - Single-aisle labs limit flexibility and efficiency
- E** Lack of Citizen-Focused Engagement

  - No space for outside visitors to experience lab functions, understand workflows, or develop interest in STEM functions
- F** Mechanical System Deficiencies & Reliability

  - Lack of separation of airflows between DOH & DEQ leads to cross-contamination risk
  - Reliability issues for power and mechanical equipment compromises testing capability



A new State Lab facility will preserve and advance our ability to  
***protect North Dakota's public health & environment.***







The proposed laboratory will provide Public Health & DEQ with:

- **Improved regulatory compliance** to ensure continued access to testing programs
- **Additional programs** and access to testing
- **Adequate space** to support current and future testing needs
- **Optimized workflows** to enable more efficient testing
- **Safe and inviting** working environment for staff.
- **State-of-the-art utility systems** with minimized cross-contamination risks
- **Citizen-focused spaces** to share our work, collaborate with universities, and inspire future scientists

# Design Process

# Existing Building Analysis




# Visual Program & Adjacency Diagrams

**Molecular Notes**  
 Sample Prep  
 (2) Refrigerator, (2) Freezer  
 (2) BSC  
 Extraction  
 (3) BSC  
 Clean Room  
**Instrumentation**  
 Access to Autoclave

**Special Microbiology Notes**  
 Virology  
 (4) M2000  
 (1) BSC  
 Alinity  
 Temp Controlled Room (23C +2)  
 Immunology - Panther  
 Requires access to autoclave  
 Door between all spaces in suite  
 required  
 Separate M2000 from Panther  
 space to avoid cyanide gas

**BSL-3 Notes**  
 Prefer flow and operation of  
 double-module BSL-3 spaces



- Department of Health
- BSL Labs
- Lab Support
- Office Space
- Shared Building Support/Mechanical
- Public/Lobby Spaces

**Environmental Notes**  
 Test Lab  
 (1) 4' Fume Hood  
 Insect Count  
 (qty) Microscopes  
 Area includes vestibule at entry  
 Media  
 (1) 4' Fume Hood  
 Access to Autoclave

**General Microbiology Notes**  
 Bacterial Test  
 Close connection to Bioterror  
 Parasite Test  
 Close connection to autoclave

**Amplitude Notes**  
 Amplitude Module 1  
 (1) Test Equip Approx 3' x 12'  
 (2) BSCs  
 (1) Dbl door fridge,  
 (1) Freezer  
 Amplitude Clean Lab  
 (1) Test Equip approx 16' x 20'

**Sequencing Notes**  
 Extraction Lab  
 (2) BSC, 100% exhaust  
 (2) BSCs  
 WGS-Clean Labs  
 (1) Fume Hood with cup sink  
 Flexible casework layouts for  
 sequencing equipment  
 Vibration sensitive equipment







**DEQ Lab Vision:**  
 Suites equipped with technology to support specific testing.  
 Each suite - Larger prep area, smaller test area. Approx 1/3 prep, 2/3 test  
 Establish size of suite based on quantity of instrumentation within - see  
 diagrams  
 Vacuum pumps - noise control required (closest for vac pumps or sound  
 insulated cabinets)  
 Prep Rooms  
 (1) or (2) fume hoods, sometimes two fume hoods, or canopy hood  
 Bench snorkels as shown on diagram

**Instrument/Test rooms**  
 Always have a sink somewhere, but have movable tables for  
 instrumentation.  
 Space for (1) refrigerator or freezer for reagent storage  
 Overhead carriers with gas connection  
 Suites discussed (Instrument qty per DEQ input)  
 1) LC, GC, GCMS - (8) Instruments  
 2) GCMS/MS - (6) Instruments  
 3) ICP, ICPMS - (6) Instruments - Low metal lab  
 4) LCMS/MS - (6) Instruments - Clean Lab, Low PFAS Lab  
 5) ICM/MS - (4) Instruments - Clean Lab  
 6) VOC - (4) Instruments - Clean Lab  
 7) FIA and IC - (6) Instruments  
 8) Petroleum - (4) Instruments  
 9) Feed/Fertilizer - (4) Instruments  
 10) Miscellaneous Testing - (4) Instruments  
 11) Kit Prep - (4) Instruments  
 12) Dirty - (4) Instruments

**Additional Functions**  
 1) Gridding  
 2) Sample Login  
 3) Admin Assistant  
 4) Demands Lab  
 5) Engines


**Sample Login Notes**  
 Dedicated dock for sample receipt  
 Sample Login  
 (2) Staff  
 Bench space for sample receipt,  
 temp and PH checks  
 (2) Fume Hood for sample prep  
 Secure Sample Storage  
 (qty) Refrigerator  
 (qty) Freezer  
 Bench space  
 High-density storage racks for  
 samples requiring chain of  
 custody  
 Sample Storage  
 Bench space  
 Refrigerator  
 Freezer  
 Storage Racks  
 Central Supply  
 Engine Room  
 Soundproofed walls  
 100% Exhaust  
 Existing equipment for octane  
 testing  
 Direct connection to exterior for  
 solvent vault  
 Demand Lab  
 Prep and testing can occur in the  
 same space.  
 Surge capacity needed due to new  
 water quality rules - 50% larger  
 than existing footprint requested  
 Grinding Lab  
 Soundproofed walls  
 100% Exhaust

**Central Utility Services - DEQ Labs**  
 RO Water  
 Compressed air (central system)  
 Plumbed Lab Gases  
 Nitrogen  
 Helium  
 Hydrogen  
 Argon  
 Oxygen  
 Acid Neutralization System  
 Backup Power with UPS  
 Data Backbone - use  
 state-of-the-art cabling, wiring,  
 etc




# Visual Program & Adjacency Diagrams (DOH Detail)

**Molecular Notes**  
**Sample Prep**  
 (2) Refrigerator, (2) Freezer  
 (2) BSC  
**Extraction**  
 (3) BSC  
 Clean Room  
**Instrumentation**  
 Access to Autoclave




**Environmental Notes**  
**Test Lab**  
 (1) 4' Fume Hood  
**Insect Count**  
 (qty) Microscopes  
 Area includes vestibule at entry  
**Media**  
 (1) 4' Fume Hood  
 Access to Autoclave

**Special Microbiology Notes**  
**Virology**  
 (4) M2000  
 (1) BSC  
 Alinity  
 Temp Controlled Room (23C +2)  
**Immunology - Panther**  
 Requires access to autoclave  
 Door between all spaces in suite required  
 Separate M2000 from Panther space to avoid cyanide gas



**General Microbiology Notes**  
**Bacterial Test**  
 Close connection to Bioterror  
**Parasite Test**  
 Close connection to autoclaves

**BSL-3 Notes**  
 Prefer flow and operation of double-module BSL-3 spaces



**Amplitude Notes**  
**Amplitude Module 1**  
 (1) Test Equip Approx 3' x 12'  
 (2) BSCs  
 (1) Dbl door fridge,  
 (1) Freezer  
**Amplitude Clean Lab**  
 (1) Test Equip approx 16' x 20'

# Visual Program & Adjacency Diagrams (DEQ Detail)

**DEQ Lab Vision:**  
 Suites equipped with technology to support specific testing.  
 Each suite - Larger prep area, smaller test area. Approx 1/3 prep, 2/3 test  
 Establish size of suite based on quantity of instrumentation within - see diagrams

Vacuum pumps - noise control required (closet for vac pumps or sound insulated cabinets)

**Prep Rooms**  
 (1) or (2) fume hoods, sometimes two fume hoods, or canopy hood  
 Bench snorkels as shown on diagram

**Instrument/Test rooms**  
 Always have a sink somewhere, but have movable tables for instrumentation.  
 Space for (1) refrigerator or freezer for reagent storage  
 Overhead carriers with gas connection


Suites discussed (Instrument qty per DEQ input)

- 1) LC, GC, GCMS - (8) Instruments
- 2) GCMS/MS - (6) Instruments
- 3) ICP, ICPMS - (6) Instruments - Low metal lab
- 4) LCMS/MS - (6) Instruments - Clean Lab, Low PFAS Lab
- 5) ICMS/MS - (4) Instruments - Clean Lab
- 6) VOC - (4) Instruments - Clean Lab
- 7) FIA and IC - (6) Instruments
- 8) Petroleum - (4) Instruments
- 9) Feed/Fertilizer - (4) Instruments
- 10) Miscellaneous Testing - (4) Instruments
- 11) Kit Prep - (4) Instruments
- 12) Dirty - (4) Instruments


**Additional Functions**

- 1) Gridding
- 2) Sample Login
- 3) Admin Assistant
- 4) Demands Lab
- 5) Engines


Typical Layout - (2) Instrument Lab



Typical Layout - (4) Instrument Lab



Typical Layout - (6) Instrument Lab



**PROGRAM SUMMARY**

PROGRAM SUMMARY	Existing		Proposed		Delta
	Staff	Square Feet (net)	Staff	Square Feet (net)	SF
<b>Main Lab Building</b>					
<i>Departments</i>					
Department of Health (DOH)	23	5,545	35	33,864	28,319
Department of Environmental Quality (DEQ)	12	7,671	16	26,571	18,900
Shared Lab Support		1,648		968	-680
Public/Lobby Spaces		0		2,209	
Office Space (Existing)		6,800			-6,800
Shared Staff Space		0		2,480	2,480
Shared Building Support/Mechanical		5,287		5,921	634
Program Contingency				2,500	
<b>Subtotal Departmental Space Needs*</b>	<b>35</b>	<b>26,951</b>	<b>51</b>	<b>74,513</b>	<b>47,562</b>
Building Gross Up (est) - walls, circulation, etc)	25%	6,258	35%	26,080	19,822
<b>Total Building Needs (GSF)</b>		<b>33,209</b>		<b>100,593</b>	<b>67,384</b>

\* Departmental Square Footage includes 35% secondary circulation gross up.

\*\* Staff headcounts include staff with dedicated office/cubicle space. Lab Techs without assigned office/cubicle are not included in these headcounts.

Existing Ancillary Support Buildings	Existing
	Square Feet (gross)
DOH/DEQ Storage Building - 2635 E Main	3,200
DOH Warehouse - 26th & Vermont	10,000
DOH Mobile Lab 1	442
DOH Mobile Lab 2	442
<b>Total Ancillary Support Building Square Footage</b>	<b>14,084</b>

<b>Total Existing Square Footage</b>	<b>47,293</b>
--------------------------------------	---------------

Space Type	Area	Comment
Lab space	53,100 sf	(A) (B) (C)
Office Space:	8,493 sf	
Training Lab and Conferencing:	2,200 sf	(D)
Support space (lab support, mechanical/electrical, circulation):	36,800 sf	(E) (F) (G)
<b>Total proposed:</b>	<b>100,593 sf</b>	

**(A) Additional Lab Space**

- Separated lab functions address cross-contamination concerns
- Dedicated space for sample receipt & storage
- Growth space for new programs

**(B) BSL-3 Growth Factors**

- Lack of vestibules/anterooms in existing
- Additional area to improve workflow

**(C) General storage/supplies co-located with labs**

- Allows more efficient utilization of storage square footage

**(D) Public-Facing Training and Conferencing**

- Space provided for visitor training and conferencing, plus training lab for staff and outside training.

**(E) DOH Warehouse Exit Strategy**

- Bulk storage space provided in program. Reduced COVID demands will drive eventual elimination of need for offsite warehouse space allowing 26th & Vermont warehouse lease to be terminated

**(F) Mechanical Equipment Strategy**

- Indoor space for boilers, fire suppression, air compressors, vacuum process chillers, etc. Rooftop chillers, air handlers, exhaust fans with service vestibules. Design team is studying potential rooftop penthouse to allow indoor mechanical units

**(G) Building Gross-Up**

- Additional gross-up to support vertical circulation, shafts, and wider hallways




# Conceptual Floor Plans



- Currently planning for three story facility
  - Level 1 - DOH/DEQ Labs, Training Labs, Warehouse
  - Level 2 - DEQ Labs & Offices
  - Level 3 - DOH Labs & Offices

# Site Selection





- Site evaluation process is ongoing, focused on state-owned sites
- Leaning towards Capitol grounds due to land cost savings, shared infrastructure, and operational cost savings

- 1 Airport 1 | Burlington Dr
- 2 Airport 2 | Airway Ave
- 3 Bank of North Dakota
- 4 Capitol Site 1 | NW
- 5 Capitol Site 2 | NE
- 6 Capitol Site 3 | SE
- 7 Bismarck Expressway
- 8 Channel Drive



Cost Estimate



- Cost estimates performed in predesign process were utilized to establish Governor’s budget request  
\$15 million (received in 2021-22 bienium)  
+ \$55 million budget request  

---

\$70 million total project budget
- State has retained Kraus Anderson Construction as construction manager at risk for the project
- SD cost estimating process is ongoing.

\*Construction costs contingent on funding approval 2Q 2023

# Operating Cost Analysis



## Energy Use

- Existing Building Energy Use Intensity = 402 kbtu/sf/yr
- Proposed Energy Use Intensity = 180-240 kbtu/sf/yr
- Energy Cost = \$ 367,000/yr (~\$3.65/sf/yr)

## Additional Operating Cost (Trash, snow removal, etc)

- Cost target dependent on site chosen and ability to share resources with adjacent state buildings
- Range of \$5-\$15/sf/yr

## Operating Cost Projection

Low: \$9/sf x 100,600 sf = \$905,000 per year

High: \$20/sf x 100,600 sf = \$2,012,000 per year



Schedule

Milestone	Date
Finalize Site Selection	Q1 2023
Funding Secured	Q2 2023
Design Complete	Q3 2023
Construction Start	Q3 2023
Construction Complete	Q4 2025
Building Occupancy	Q1 2026

All approximate dates contingent on funding

Thanks!  
Question/Answer