Transcribed from a handwritten note:

1-10-13

Equality Township, Williams County

Estimated cost to resurface 1 mile of gravel road, 3 inches (deep) X 30' (wide)

1467 yards of gravel @ $12/yard	$17,604
1467 yards of gravel hauling @ $6/yard	$8,802
Water Truck 20 hours @ $130/hour	$2,600
10 Loads of Water X 6,000 gal/load	$600
Blade Work 32 hours X $200	$6,400
(TOTAL) 1 Mile	**$36,006**
(PROJECT) X 6 Miles	**$216,036**

Paul Weyrauch

Chairman of Equality Township

Board of Supervisors

Presented by Larry Syverson, North Dakota Township Officers Association